

**Alabama Department of Transportation
Proposal Item Summary**

031. STPAA-HSIP-0027(519)

HENRY COUNTY

Contract Time: 45 Working Days

DBE Goal Percent: 2.00

for constructing the Safety Widening, Planing, Resurfacing, and Traffic Stripe on SR-27 from the intersection of SR-1 (US-431) to the junction of SR-10 in Abbeville. Length 2.741 mi.

The Bracket Estimate on this project is from \$1,306,319 to \$1,596,613.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$8.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C010	64	SQYD	Removing Concrete Driveway
206D001	250	LF	Removing Guardrail
206E008	4	Each	Removing Guardrail End Anchor (All Type)
209A000	5	Each	Mailbox Reset, Single
212A000	130	STA	Machine Grading Shoulders
401B100	17,248	SQYD	Bituminous Treatment E (With Polymer Additive)
405A000	3,777	Gal	Tack Coat
408A052	37,829	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A361	4,978	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424A370	176	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B663	503	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B701	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range C/D
430B043	60	Ton	Aggregate Surfacing (1" Down, Crusher Run)
502A000	400	LB	Steel Reinforcement
524B011	7	CUYD	Culvert Concrete Extension (Cast In Place)
600A000	1	LS	Mobilization
630A001	150	LF	Steel Beam Guardrail, Class A, Type 2
630C080	4	Each	Guardrail End Anchor, Type 20 Series (MASH)
630G003	38	LF	Steel Beam Guardrail for Culvert, Class A, Type 2, Case 3
650A000	653	CUYD	Topsoil
652A100	3	Acre	Seeding
652C000	8	Acre	Mowing
656A010	3	Acre	Mulching
659C002	270	SQYD	Erosion Control Product, Type S2
665A000	3	Acre	Temporary Seeding
665B001	5	Ton	Temporary Mulching
665G000	100	Each	Sand Bags
665J002	1,000	LF	Silt Fence
665O001	1,000	LF	Silt Fence Removal
665Q002	1,000	LF	Wattle
666A001	3	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 76,000.00)
701A227	8	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)

Item No.	Quantity	Units	Description
701A230	5	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	661	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	1	Mile	Broken Temporary Traffic Stripe
701C001	12	Mile	Solid Temporary Traffic Stripe
701D007	1	Mile	Solid Traffic Stripe Removed (Paint)
701D008	1	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	1	Mile	Broken Traffic Stripe Removed (Paint)
701D015	1	Mile	Broken Traffic Stripe Removed (Plastic)
701G252	300	LF	Solid White, Class 2, Type A Traffic Stripe (5" Wide) (Rumble Strip)
703A002	3,881	SQFT	Traffic Control Markings, Class 2, Type A
703B002	681	SQFT	Traffic Control Legends, Class 2, Type A
703D001	2,237	SQFT	Temporary Traffic Control Markings
703E001	546	SQFT	Temporary Traffic Control Legends
705A030	37	Each	Pavement Markers, Class A-H, Type 2-C
705A032	248	Each	Pavement Markers, Class A-H, Type 1-B
705A037	130	Each	Pavement Markers, Class A-H, Type 2-D
705A038	96	Each	Pavement Markers, Class A-H, Type 2-E
726A000	160	LF	Portable Concrete Safety Barriers, Type 6
726D000	2	Each	Portable Impact Attenuator (Portable Impact Attenuator)
730H001	3,200	LF	Loop Wire
740B000	1,255	SQFT	Construction Signs
740C000	108	SQFT	Special Construction Signs
740D000	50	Each	Channelizing Drums
740E000	350	Each	Cones (36 Inches High)
740M001	350	Each	Ballast For Cone
740O000	1	Each	Pilot Car