

**Alabama Department of Transportation
Proposal Item Summary**

032. STPAA-HSIP-0162(505)

WILCOX COUNTY

Contract Time: 40 Working Days

DBE Goal Percent: 1.50

for constructing the Safety Widening, Resurfacing, Culvert Extension, Guardrail Installation, and Traffic Stripe on SR-162 from a point 0.250 mile west of Dixon Creek (MP 10.744) to the junction of SR-28 northwest of Miller's Ferry. Length 3.152 mi.

The Bracket Estimate on this project is from \$1,272,022 to \$1,554,694.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$8.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206E008	4	Each	Removing Guardrail End Anchor (All Type)
212A000	322	STA	Machine Grading Shoulders
405A000	4,405	Gal	Tack Coat
408A052	37,270	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A341	4,330	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424A350	100	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	850	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B677	1,250	Ton	Superpave Bituminous Concrete Lower Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range A/B
428A001	7	Mile	Scoring Bituminous Pavement Surface
430B043	876	Ton	Aggregate Surfacing (1" Down, Crusher Run)
502A000	2,198	LB	Steel Reinforcement
524B011	20	CUYD	Culvert Concrete Extension (Cast In Place)
600A000	1	LS	Mobilization
610C001	25	Ton	Loose Riprap, Class 2
610D003	60	SQYD	Filter Blanket, Geotextile
630C079	2	Each	Guardrail End Anchor, Type 13 (MASH)
630C080	2	Each	Guardrail End Anchor, Type 20 Series (MASH)
631C010	250	LF	Guardrail Reset
631E003	3	Each	Guardrail End Anchor, Type 13, Reset
650A000	565	CUYD	Topsoil
652A100	4	Acre	Seeding
652C000	48	Acre	Mowing
654A000	354	SQYD	Solid Sodding
656A010	4	Acre	Mulching
665B001	12	Ton	Temporary Mulching
665J002	250	LF	Silt Fence
665O001	250	LF	Silt Fence Removal
665Q002	150	LF	Wattle
666A001	1	Acre	Pest Control Treatment
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 66,615.00)
701A227	7	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)

Item No.	Quantity	Units	Description
701A230	4	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	3	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	7	Mile	Broken Temporary Traffic Stripe
701C001	18	Mile	Solid Temporary Traffic Stripe
701G146	1,148	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G150	574	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G154	238	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	1,386	LF	Solid Traffic Stripe Removed (Tape)
701H007	574	LF	Broken Traffic Stripe Removed (Tape)
705A030	109	Each	Pavement Markers, Class A-H, Type 2-C
705A032	122	Each	Pavement Markers, Class A-H, Type 1-B
705A037	114	Each	Pavement Markers, Class A-H, Type 2-D
740B000	1,028	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums
740E000	100	Each	Cones (36 Inches High)
740M001	100	Each	Ballast For Cone
740O000	1	Each	Pilot Car