

**Alabama Department of Transportation
Proposal Item Summary**

038. STPPC-4123(252)

LEE COUNTY

Contract Time: 35 Working Days

DBE Goal Percent: 0.50

for constructing the Resurfacing, Guardrail Installation, and Traffic Stripe on CR-240 from a point near the Hospilika Creek Bridge to the junction of County Line Road south of Smiths Station. Length 4.671 mi.

The Bracket Estimate on this project is from \$1,008,808 to \$1,232,988.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$10.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	100	LF	Removing Guardrail
405A000	10,007	Gal	Tack Coat
424A356	3,823	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424B701	2,889	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range C/D
430B043	965	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
630A001	125	LF	Steel Beam Guardrail, Class A, Type 2
630A004	60	LF	Steel Beam Guardrail, Class B, Type 2
630C022	4	Each	Guardrail End Anchor, Type Special
630C077	1	Each	Guardrail End Anchor, Type 8 (MASH)
630C080	3	Each	Guardrail End Anchor, Type 20 Series (MASH)
652A100	1	Acre	Seeding
656A010	1	Acre	Mulching
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 53,000.00)
701A227	10	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A235	8	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	5	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701B205	1,323	LF	Dotted, Class 2, Type A, Traffic Stripe
701C000	9	Mile	Broken Temporary Traffic Stripe
701C001	22	Mile	Solid Temporary Traffic Stripe
703A002	3,845	SQFT	Traffic Control Markings, Class 2, Type A
703B002	359	SQFT	Traffic Control Legends, Class 2, Type A
703D001	1,794	SQFT	Temporary Traffic Control Markings
705A030	272	Each	Pavement Markers, Class A-H, Type 2-C
705A032	610	Each	Pavement Markers, Class A-H, Type 1-B
705A037	537	Each	Pavement Markers, Class A-H, Type 2-D
705A038	215	Each	Pavement Markers, Class A-H, Type 2-E
740B000	800	SQFT	Construction Signs
740D000	250	Each	Channelizing Drums
740E000	25	Each	Cones (36 Inches High)
740M001	25	Each	Ballast For Cone
740O000	1	Each	Pilot Car