

Alabama Department of Transportation - Proposal Questions and Answers

Project Number ATRP2-42-2020-042

Call # 032

County

LIMESTONE

Project Description

for constructing the Roadway Improvements (Adding/Extending Left and Right Turn Lanes) on SR-2 (US-72) at Mooresville Road in Athens. Length 0.156 mi. In the County of LIMESTONE, State of Alabama.

As of: 6/13/2022

| Item | Question | Answer |
|------|---|---|
| 1 | Could you please clarify the modifications intended for the following structures: 621A022 - structures #10, #3, and #16; 621C029 - structures #14, #14A, #15, #17, and #19; 621C130 - structure #18. We do not find special project details that indicate required modifications. | Structures 3, 10, and 16 are modified since the minimum 6" clearance (shown on referenced drawing JB-620-B) between the top of pipe and bottom of junction box cannot be achieved. Structures 14,14A,15,17,18,19 are modified since these inlets will not have concrete median barrier on them as shown on the I-621-E1 drawing but rather a 2' monolithic island on them instead. This information may be obtained in the current plan assembly by referencing the plan sheets in conjunction with the drainage sections pertaining to these structures. It was discovered that standard drawing index 62118 needed to be removed and index 62123 needed to be added as reference in this plan assembly. See flagged revision # 1. |
| 2 | | |
| 3 | | |
| 4 | | |
| 5 | | |
| 6 | | |
| 7 | | |