

**Alabama Department of Transportation
Proposal Item Summary**

062. STPAA-0069(556)

CLARKE COUNTY

Contract Time: 40 Working Days

DBE Goal Percent: 3.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-69 from Cantuche Church (MP 15.184) to the junction of SR-12 (US-84) in Coffeerville. Length 7.071 mi.

The Bracket Estimate on this project is from \$1,131,243 to \$1,382,630.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$5.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
405A000	11,960	Gal	Tack Coat
407B000	7	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	113,739	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A341	9,953	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424A350	645	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B643	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
428A001	14	Mile	Scoring Bituminous Pavement Surface
430B043	600	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
650A000	200	CUYD	Topsoil
652A100	1	Acre	Seeding
652C000	35	Acre	Mowing
656A010	1	Acre	Mulching
665J002	200	LF	Silt Fence
665O001	200	LF	Silt Fence Removal
665Q002	200	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 40,000.00)
701A227	15	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	14	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C002	4	Mile	Broken Temporary Traffic Stripe (Paint)
701C003	81	Mile	Solid Temporary Traffic Stripe (Paint)
701G146	1,748	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	1,748	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	3,496	LF	Solid Traffic Stripe Removed (Tape)
703A002	1,319	SQFT	Traffic Control Markings, Class 2, Type A
703B002	80	SQFT	Traffic Control Legends, Class 2, Type A
703D002	1,708	SQFT	Temporary Traffic Control Markings (Paint)
703E002	160	SQFT	Temporary Traffic Control Legends (Paint)
705A030	20	Each	Pavement Markers, Class A-H, Type 2-C
705A032	220	Each	Pavement Markers, Class A-H, Type 1-B
705A037	925	Each	Pavement Markers, Class A-H, Type 2-D
705A038	50	Each	Pavement Markers, Class A-H, Type 2-E
740B000	427	SQFT	Construction Signs

Item No.	Quantity	Units	Description
740E000	100	Each	Cones (36 Inches High)
740M001	100	Each	Ballast For Cone
740O000	1	Each	Pilot Car
742A001	2	Each	Portable Changeable Message Sign, Type 2