

**Alabama Department of Transportation  
Proposal Item Summary**

**070. STPAA-HSIP-0123(511)**

**DALE COUNTY**

Contract Time: 40 Working Days

DBE Goal Percent: 10.00

for constructing the Safety Widening, Resurfacing, Guardrail Installation, and Traffic Stripe on SR-123 from the junction of SR-51 in Ariton to the junction of SR-53 (US-231). Length 3.607 mi.

The Bracket Estimate on this project is from \$1,253,926 to \$1,532,576.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$8.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206C010	269	SQYD	Removing Concrete Driveway
206D001	4,100	LF	Removing Guardrail
206E008	24	Each	Removing Guardrail End Anchor (All Type)
209A000	3	Each	Mailbox Reset, Single
210D021	891	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
212A000	379	STA	Machine Grading Shoulders
405A000	11,200	Gal	Tack Coat
407B000	4	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	51,511	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A341	5,005	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424A350	152	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B648	1,451	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B700	2,119	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range A/B
428A001	7	Mile	Scoring Bituminous Pavement Surface
600A000	1	LS	Mobilization
630A001	4,750	LF	Steel Beam Guardrail, Class A, Type 2
630C022	4	Each	Guardrail End Anchor, Type Special
630C080	20	Each	Guardrail End Anchor, Type 20 Series (MASH)
650A000	2,524	CUYD	Topsoil
652A100	11	Acre	Seeding
652C000	36	Acre	Mowing
656A010	11	Acre	Mulching
659C002	450	SQYD	Erosion Control Product, Type S2
665A000	4	Acre	Temporary Seeding
665B001	11	Ton	Temporary Mulching
665J002	950	LF	Silt Fence
665O001	950	LF	Silt Fence Removal
665Q002	1,180	LF	Wattle
666A001	11	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 66,125.00)
701A227	8	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	3	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	3	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)

Item No.	Quantity	Units	Description
701C000	8	Mile	Broken Temporary Traffic Stripe
701C001	23	Mile	Solid Temporary Traffic Stripe
701D007	1	Mile	Solid Traffic Stripe Removed (Paint)
701D008	1	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	1	Mile	Broken Traffic Stripe Removed (Paint)
701D015	1	Mile	Broken Traffic Stripe Removed (Plastic)
701G146	244	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	122	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
703A002	216	SQFT	Traffic Control Markings, Class 2, Type A
703B002	137	SQFT	Traffic Control Legends, Class 2, Type A
703D001	216	SQFT	Temporary Traffic Control Markings
703E001	273	SQFT	Temporary Traffic Control Legends
705A032	95	Each	Pavement Markers, Class A-H, Type 1-B
705A037	259	Each	Pavement Markers, Class A-H, Type 2-D
740B000	688	SQFT	Construction Signs
740C000	23	SQFT	Special Construction Signs
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone
740O000	1	Each	Pilot Car