

**Alabama Department of Transportation
Proposal Item Summary**

078. STPNU-3317(250)

HALE COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 1.00

for constructing the Resurfacing (Full Depth Reclamation) and Traffic Stripe on CR-54 from the junction of SR-69 to the junction of SR-25 southwest of Greensboro. Length 2.210 mi.

The Bracket Estimate on this project is from \$526,725 to \$643,775.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
210D021	400	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
302A000	28,403	SQYD	Full Depth Reclamation, 10 Inches Thick
302B000	724	Ton	Portland Cement For Full Depth Reclamation
401B108	25,821	SQYD	Bituminous Treatment G (With Polymer Additive)
405A000	2,593	Gal	Tack Coat
407B000	3	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A340	2,189	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	642	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
665F000	40	Each	Hay Bales
665J002	1,195	LF	Silt Fence
665O001	1,195	LF	Silt Fence Removal
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 28,000.00)
701A030	4	Mile	Solid White, Class 2T, Type A Traffic Stripe
701A034	2	Mile	Solid Yellow, Class 2T, Type A Traffic Stripe
701A044	3	Mile	Broken Yellow, Class 2T, Type A Traffic Stripe
701C000	3	Mile	Broken Temporary Traffic Stripe
701C001	7	Mile	Solid Temporary Traffic Stripe
703A004	122	SQFT	Traffic Control Markings, Class 2T, Type A
705A032	50	Each	Pavement Markers, Class A-H, Type 1-B
705A037	150	Each	Pavement Markers, Class A-H, Type 2-D
740B000	301	SQFT	Construction Signs
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone
740O000	1	Each	Pilot Car