

**Alabama Department of Transportation  
Proposal Item Summary**

---

**079. STPNU-3618(250)**

**JACKSON COUNTY**

Contract Time: 30 Working Days

DBE Goal Percent: 4.00

for constructing the Planing, Resurfacing, and Traffic Stripe on CR-59 from the Dekalb County Line to the intersection of CR-16 east of Dutton. Length 1.956 mi.

The Bracket Estimate on this project is from \$352,938 to \$431,368.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

*The Principal Items of work are approximately as follows:*

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
405A000	900	Gal	Tack Coat
407B000	2	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	303	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
424A341	2,412	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B644	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424C344	600	Ton	Superpave Bituminous Concrete Base Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	494	Ton	Aggregate Surfacing (1" Down, Crusher Run)
433A000	22,963	SQYD	Scrub Seal
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 19,900.00)
701A231	4	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	3	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701C000	2	Mile	Broken Temporary Traffic Stripe
701C001	5	Mile	Solid Temporary Traffic Stripe
703A002	204	SQFT	Traffic Control Markings, Class 2, Type A
705A032	33	Each	Pavement Markers, Class A-H, Type 1-B
705A037	194	Each	Pavement Markers, Class A-H, Type 2-D
740B000	534	SQFT	Construction Signs
740E000	25	Each	Cones (36 Inches High)
740M001	25	Each	Ballast For Cone
740O000	1	Each	Pilot Car