

**Alabama Department of Transportation  
Proposal Item Summary**

---

**080. STPNU-4614(257)**

**MARENGO COUNTY**

Contract Time: 30 Working Days

for constructing the Resurfacing and Traffic Stripe on CR-30 from the junction of CR-32 southwest of Magnolia to the junction of CR-36 at the Wilcox County Line. Length 3.999 mi.

The Bracket Estimate on this project is from \$704,780 to \$861,397.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

*The Principal Items of work are approximately as follows:*

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
405A000	2,820	Gal	Tack Coat
407B000	4	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A340	3,200	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	3,170	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	2,820	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 38,000.00)
701A030	8	Mile	Solid White, Class 2T, Type A Traffic Stripe
701A034	7	Mile	Solid Yellow, Class 2T, Type A Traffic Stripe
701A044	5	Mile	Broken Yellow, Class 2T, Type A Traffic Stripe
701C000	5	Mile	Broken Temporary Traffic Stripe
701C001	15	Mile	Solid Temporary Traffic Stripe
703A004	40	SQFT	Traffic Control Markings, Class 2T, Type A
705A032	75	Each	Pavement Markers, Class A-H, Type 1-B
705A037	550	Each	Pavement Markers, Class A-H, Type 2-D
740B000	424	SQFT	Construction Signs
740O000	1	Each	Pilot Car