

**Alabama Department of Transportation  
Proposal Item Summary**

---

**081. STPNU-5018(250)**

**MONROE COUNTY**

Contract Time: 30 Working Days

DBE Goal Percent: 1.00

for constructing the Resurfacing and Traffic Stripe on CR-23 from the East City Limits of Frisco City to the West City Limits of Excel. Length 2.336 mi.

The Bracket Estimate on this project is from \$524,119 to \$640,590.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206E019	1	Each	Removing Guardrail End Anchor (Type 10)
405A000	6,568	Gal	Tack Coat
407B000	3	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A340	2,090	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B639	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B643	3,085	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
600A000	1	LS	Mobilization
630C070	1	Each	Guardrail End Anchor, Type 10 Series
650A000	1,294	CUYD	Topsoil
652A100	4	Acre	Seeding
656A010	4	Acre	Mulching
665F000	25	Each	Hay Bales
665J002	500	LF	Silt Fence
665O001	500	LF	Silt Fence Removal
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 29,000.00)
701A231	5	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	4	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	2	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701C000	2	Mile	Broken Temporary Traffic Stripe
701C001	15	Mile	Solid Temporary Traffic Stripe
703A002	40	SQFT	Traffic Control Markings, Class 2, Type A
705A032	50	Each	Pavement Markers, Class A-H, Type 1-B
705A037	250	Each	Pavement Markers, Class A-H, Type 2-D
740B000	303	SQFT	Construction Signs
740E000	25	Each	Cones (36 Inches High)
740M001	25	Each	Ballast For Cone
740O000	1	Each	Pilot Car