

**Alabama Department of Transportation
Proposal Item Summary**

085. STPNU-6618(251)

WILCOX COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 3.00

for constructing the Resurfacing and Traffic Stripe on CR-37 from the intersection of CR-31 northeast of Camden to the junction of CR-43 and on CR-43 from the junction of CR-37 to the junction of Deer Run Drive. Length 2.400 mi.

The Bracket Estimate on this project is from \$325,472 to \$397,799.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
405A000	2,817	Gal	Tack Coat
407B000	3	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A346	3,020	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B638	425	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
600A000	1	LS	Mobilization
610D003	100	SQYD	Filter Blanket, Geotextile
630A034	160	LF	Steel Beam Guardrail, Class A, Type 2 (8'-0" Post)
630C080	4	Each	Guardrail End Anchor, Type 20 Series (MASH)
650A000	300	CUYD	Topsoil
652A100	2	Acre	Seeding
656A010	2	Acre	Mulching
665Q002	200	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 18,000.00)
701A030	5	Mile	Solid White, Class 2T, Type A Traffic Stripe
701A034	5	Mile	Solid Yellow, Class 2T, Type A Traffic Stripe
701A044	1	Mile	Broken Yellow, Class 2T, Type A Traffic Stripe
701C000	1	Mile	Broken Temporary Traffic Stripe
701C001	5	Mile	Solid Temporary Traffic Stripe
703A004	120	SQFT	Traffic Control Markings, Class 2T, Type A
705A032	75	Each	Pavement Markers, Class A-H, Type 1-B
705A037	316	Each	Pavement Markers, Class A-H, Type 2-D
740B000	303	SQFT	Construction Signs
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone
740O000	1	Each	Pilot Car